

ATTACHMENT 8

EROSION CONTROL PLAN

To ensure that environmental impacts and potential for erosion/sedimentation are minimized and/or avoided to the extent practicable, the following protocols will be undertaken:

- Prior to construction, the Contractor will be required to submit a Work Plan describing their proposed construction approach, methodology, and equipment to be used. This plan will be reviewed by the Owner and/or their representative(s) to ensure compliance with applicable regulatory requirements and BMPs.
- If necessary, turbidity curtain(s) will be deployed around area(s) of active over-water construction prior to initiation of any construction activities to prevent migration of sediment or other materials outside of the active work area(s).
- Any land disturbing activities associated with the shoreward extension of the existing pier, laydown/storage areas, etc. shall avoid encroachment into any wetland areas outside of the permitted impact area.
- Silt fence(s) will be installed downgradient of any disturbed upland areas and/or stockpile areas to minimize potential for erosion or sedimentation during construction activities.
- Temporary seeding/mulching will be used to stabilize any disturbed upland areas that have not been prepared for final seeding or stabilization.
- Permanent seeding/mulching will be utilized to stabilize any disturbed upland areas at the conclusion of the construction activities.